

Clause	Description	Requirement	Supporting Document
NDW 5	Excavation and Installation	All excavation and installations shall be in accordance with the drinking water system requirements as shown in the WSCM	
NDW 6	Product Installation	All product handling and installation shall be in accordance with the drinking water system as shown in the WSCM and WSA 03 (incl SA Water Supplement)	
NDW 7.1	Tapping of Mains	Pre-tapped connectors are to be used to provide services on all new DN100 and DN150 mains. Tapping bands are only permitted on larger size mains and for connections to existing mains. Main cocks are not required except for under pressure tapping applications	
NDW 7.2	Installation of Property Services	In new subdivisions, mains and the property connections shall be laid at the same time. Layout and positioning of property services shall be in accordance with WSCM Drawings Section D. Property services crossing a road do not have to be placed within a duct.	
NDW 8.2	Testing	Pressure testing is to be the same as detailed in the WSCM for drinking water.	
ADDITIONAL REQUIREMENTS			
	Training Requirements	Same as WSCM requirements for Drinking Water	
	Quality System	Same as WSCM requirements for Drinking Water	
	“Notice of Intent” Requirements	Same as WSCM requirements for Drinking Water	
	Issue of “Certificate of Practical Completion”	Same as WSCM requirements for Drinking Water	
	Constructor’s Indemnification requirements	Same as WSCM requirements for Drinking Water	
	Defect Advice Sheet	See WSA 03 Supplementary Documentation	
	Corrective Action Request	See WSA 03 Supplementary Documentation	
ANNEXURES			
Annex A	As-Constructed Symbols and Abbreviations (1 page)		
Annex B	As-Constructed Mains Reporting Data (3 pages)		
Annex C	Typical As-Constructed Drawing (1 page)		